

# Final Draft Zoning Ordinance and Zoning Map

# Briefing to Mayor and Council



#### **Presentation Outline**

- Background of Process
- Highlights of Planning
   Commission Recommendations
- Zoning Map
- Topics for further study
- Development moratorium



#### **Background:**

- •2005-06 Mayor and Council worksessions on zoning issues staff white papers
- •RORZOR Committee appointed by Mayor and Council in February, 2006
- •RORZOR completes work on draft ordinance and maps in September, 2007



- •Mayor and Council introduce text amendment and map amendment on October 8, 2007
- Planning Commission holds
   public hearings in January, 2008
- •Planning Commission approves final draft text and revised maps on May 21, 2008 for transmittal to Mayor and Council




# **Highlights of Planning Commission Recommendations**

- •Residential Areas: Home-Based Business Enterprises (HBBEs); Mansionization; Park Zone
- •Mixed-Use Zones: Building Heights; Stonestreet Avenue; Public Use Space; Layback Slope; Sidewalks;



- •Grandfathering & Nonconformities: Grandfathering for mixed-use zones & moderate density residential zones
- •Parking Standards: Set maximums; Allow more reductions; Design Manual
- •Historic Site Provisions: Defined role for HDC in project review; Delete "50-Year" rule



- •Signs: Consider a comprehensive review of sign provisions
- •Planned Development Zones: Treatment of existing Special Developments
- •Master Plan Recommendations: Changes recommended per draft Twinbrook Neighborhood Plan and pending Rockville Pike Plan



ordinance

- •Environmental Issues: Encroachments for alternative energy sources; floodplains; "Green Building"
- •Items Needing Further Consideration: Future "Green Building" ordinance; grading of residential lots;

Development Moratorium: Extension of moratorium; partial modification; Rockville Pike area



### Home-Based Business Enterprises (Sec. 25.09.07):

- •Create a no-impact HBBE Up to 10 visits per week
- No visitor logs
- Limit allowable floor area to 49% of total
- Use existing accessory buildings



- •Major HBBE's (more than 20 visits per week and/or up to 2 non-resident employees are a Special Exception
- Existing legal HBBEs allowed to continue



#### "Mansionization" (Sec. 25.10.08):

- Retain most RORZOR recommendations.
- •Allow additional height up to 40' to peak for alternative energy generation/solar access with site plan review by Commission.
- •No grandfathering proposed in singleunit detached residential zones



#### Park Zone (Sec. 25.14.06):

- Park Zone modified as recommended by Recreation and Parks
- •Commission recommends that the Park Zone be shown on all City-owned park areas, including those within the proposed PD areas
- •Park Zone recommended to placed on all public school sites.



#### **Mixed-Use Zones** (Article 13):

- Mixed-Use Transit District (MXTD)
- Mixed-Use Corridor District (MXCD)
- Mixed-Use Employment (MXE)
- Mixed-Use Business (MXB)
- Mixed-Use Neighborhood Commercial (MXNC)
- Mixed-Use Commercial (MXC)
- Mixed-Use Transition (MXT)



Existing Zones			Proposed Zones		
Zone	Bldg. Height		Mixed-	Bldg.	Bldg.
	Std.	Optional	Use Zone	Height	Height
				(RORZOR)	(Plan.
					Comm.)
TC-1	45	N/A	MXTD	120°	120°
TC-2	75°	N/A			(150° with
TC-3	75	100°			conditions)
TC-4	100°	235			
RPC	35	75/110	MXCD	75	75
RPR	110°	N/A			
C-2	75	N/A	MXNC	50°	45
					(65' with
		10			conditions)
O-1	75	90°	MXE	120°	120°
O-3	3 <i>5</i> °	N/A			
I-3	35	125			
I-1	40°	N/A	MXB	55	55
I-2	40°	N/A			
I-4	40°	N/A			
C-1	30°	N/A	MXC	30°	30°
O-2	35	N/A	MXT	35	35
C-T	35/40	N/A			



- •Building heights proposed to be more flexible (Sec. 25.13.05.2):
  - No upper-story setbacks
  - •In MXTD, height along street frontage limited to 65 feet unless master plan recommends more height.
  - •In MXTD, heights up to 150 feet allowed where recommended in the master plan or with added enhancements



- •Building height in MXCD Zone limited to 75'. No additional height flexibility pending outcome of Rockville Pike Plan recommendations.
- •Building height in MXNC Zone reduced to 45'. May go to 65' if recommended in master plan.



#### **Stonestreet Avenue Corridor:**

- •Revised the zoning recommendation from MXT to MXB on the east side of N. Stonestreet Avenue
- •Added new land use categories Home Improvement Service; Non-Medical Research Laboratories; Archival record storage
- •Recommends rezoning existing convenience store on S. Stonestreet to R-60




- •Public Use Space (Sec. 25.13.05.5): Set at 20% for all mixed-use zones.
  - •Sites <40,000 sq. ft., height not exceeding 65', and no residential may elect to use fee-in-lieu to meet all public use space.
  - •Sites with height above 65' must provide 10% public use space on-site.



- •Sites >40,000 sq. ft. must provide at least 10% public use space on-site. Balance may be provide via fee-in-lieu
- •Sites <40,000 sq. ft. and with residential uses must provide at least 10% public use space



#### **Layback Slope**





- •Commission recommends not applying layback slope where adjoining residential property is not developed with residential uses private schools, country clubs, etc.
- •Apply layback slope where adjoining residential includes townhouses.



- •Sidewalks (Sec. 25.17.05): Commission recommends that sidewalk design recommendations be guidelines rather than standards. Flexibility needed based on site conditions, character of adjoining development, etc.
- •Maintain 7' tree lawn area and 6' clear pedestrian path where possible.



# Nonconformities and Grandfathering (Secs. 25.11.04.d & 25.13.05.d):

- •Provide a grandfather provision for the medium-density residential zones (Townhouses and multi-unit residential) and for the Mixed-Use zones.
- •Development that conforms to the current zone standards will be considered conforming



- •Any extensions or additions beyond 5% of the pre-existing floor area must conform to the new zone standards.
- •Total demolition requires new development to conform to the new standards.



#### **Parking:**

- •Commission recommends limited parking in front in MXTD Zone where ground floor retail is provided (Sec. 25.13.07.a.6).
- •Set MAXIMUM parking standards for most commercial/industrial zones (Sec. 25.16.03.e).
- •No limit on amount of parking reductions allowed (Sec. 25.16.03.g).



- •Allow for parking reductions on small lots where full provision would hinder redevelopment.
- •Consider parking districts to provide public parking.
- •Consider allowing some on-street parking to count towards parking requirements.



# <u>Historic Site Provisions</u> (Secs. 25.07.02 & 25.14.01):

- •Delete the "50-Year Rule".
- •Define HDC role in Site Plan Review Process.
- •Early HDC evaluation for new developments to identify possible historic sites.
- •Exterior changes restricted during evaluation process.



#### **Signs (Art. 18):**

•Commission recommends comprehensive review of sign provisions after adoption of revised code.



#### **Planned Development Zones:**

- •Created to cover existing Special Development Procedure projects PRUs, PDPs, CPDs, etc. (Sec. 25.14.07)
- •Retains the original development approvals, with any amendments.
- •Designated underlying zones established for future development not currently approved with use permit or detailed application.



### **Zoning Changes Based on Twinbrook Draft Master Plan Recommendations:**

- •Reduce normal height in MXNC from 50' to 45'; allow added height up to 65' if recommended in master plan.
- •Apply MXB Zone instead of I-L Zone to Avalon Bay property on Halpine Road.



- •Retain R-60 Zone on Taylor Property on Halpine Road.
- •Apply MXC Zone to Burgundy Park Shopping Center.
- •Make "C" Zone a mixed-use zone, as MXC; allow single-unit detached residential; multi-family above the ground level; no alcoholic beverage sales off-site when adjoining single-family residential.




#### For Proposed Rockville Pike Plan:

•No height flexibility in MXCD Zone pending recommendations from the Plan.



#### **Environmental Issues:**

- •Added language (Sec. 25.09.06). to allow some height encroachments for alternative energy structures (solar panels, etc.).
- •Exclude all 100-year floodplains from the density calculations (Sec. 25.03.03.c.6.b).






# Items Needing Future Consideration by Mayor and Council:

•Commission recommends that the fee-in-lieu fees are set a levels sufficient to generate substantial funds for acquisition of needed open space areas.



- •Consider moving the parking design provisions (Sec. 25.16.06) into a separate design manual.
- •Recommend continuing to consider a "Green Building Ordinance".




#### **Items of Staff Concern**

- •Height measurement in cases where lot drops below street grade. Public Works recommends most storm water should drain to street, which would mean regrading of lots.
- •Modification of impervious surface limits in residential zones



- •Mapping of Park Zone on public school sites
- •Administration of public use space provisions in mixed-use zones



#### **Development Moratorium**

- Set to expire June 30.
- Possible Options:
  - •Continue the moratorium until adoption
  - •Modify the moratorium to allow minor impact projects: variances; special exceptions that do not require use permit; minor subdivisions (up to 3 lots)



•Rockville Pike Plan: Keep present zoning & establish a moratorium just for the Pike Plan area until new form- based zoning districts are adopted



#### **Future Schedule**

- Public Hearing: June 16 & June 30
- •Joint worksession with Planning Commission: July 7
- •Mayor and Council worksessions: July 14 & July 16
- Projected adoption: August 4, 2008